WorkMaster 450mm Step Platform FPL-AT 1.2

Technical Data Sheet

| PROPERTIES | |
|-----------------------------|---------------------------------------|
| ☑ Standards | AS/NZS 1892.3 / ANSI A 14.5-2000 |
| Load Rating | 150kg |
| # Electrical Properties | Complies to AS/NZS 1892.3 Section 2.4 |
| | 130 Degrees Celsius |
| Chemical Resistance | Tested to AS/NZS 1892.3 |
| Accelerated Weathering Test | Tested to AS 2331.3.1 |
| ☑ Warranty | 3 years from date of manufacturing |

MEASUREMENTS

| Meight | 20.8kg |
|----------------------------|-------------------------------------|
| | 0.305m |
| ♦ Open Height | 2.07m |
| ४ Closed Height | 2.34m |
| → Platform Height | 1.2m |
| | 0.9m above platform |
| >K Closed Width | 0.2m |
| K>I Width with Satbilisers | Extended 0.93m/Fully Extended 1.32m |
| Number of Steps | 4 including platform |

COMPONENTS

| Fibreglass: ISO-PE resin with e-glass fibres |
|--|
| Round: Alloy 6060 / Mg 0.35-0.6 / Ti 0.10% |
| 35% GF Nylon / Poly Urethane Tread |
| Alloy 5052/5251 / Mg 2.2-2.8 / Ti 0% |
| Alloy 5083-H116 / Mg 4.0-4.9 / Ti 0-0.15% |
| Alloy 6463-T6 / Mg 0.3-0.9 / Ti 0% |
| Alloy 5083-H116 / Mg 4.0-4.9 / Ti 0-0.15% |
| Alloy 6463-T6 / Mg 0.3-0.9 / Ti 0% |
| Polyethylene |
| Alloy 5052/5251 / Mg 2.2-2.8 / Ti 0% |
| Round: Alloy 6060 / Mg 0.35-0.6 / Ti 0.10% |
| Zinc Plated Low Carbon Steel |
| Plated Mild Steel with gold passivate |
| Plated Mild Steel with gold passivate |
| |

| Product Code | FPL-AT 1.2 |
|-------------------------------|-------------------------------------|
| Manufacturer's Name | Branach Manufacturing Pty Ltd |
| Phone Number | +61 3 9761 6633 |
| Certified By (Name, Title) | Mike Walsh Chief Design Engineer |
| Last Updated | 11/07/2024 |



